

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X</u> R. <u>31</u> W.	#M-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 19, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Section Corner 7, 12, 13, & 18, T44N, R30-31W
- Tamarack post (Not found. See B for subsequent monument.)
- Tamarack 6 S41W 69 (Not found. No subsequent accessories found.)
- Tamarack 8 S65W 96 (Not found. No subsequent accessories found.)
- Tamarack 7 N75W 1.05 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: As the true corner is presently in Crescent Pond, under water, a search for the original post or accessories could not be made. Corner position computed by proportionate measurement between original corners 239.6745 ch. S and 79.8865 ch. N, adjusted slightly to the westward of the straight line between them to secure better harmony with swamp edges N of the corner. Distances E to pond edge, hill, and valley are 11.05 ch., 13.60 ch., and 20.30 ch., respectively, compared to 10.60 ch., 13.60 ch., and 20.60 ch., respectively, in the original record. Distance S to a stream crossing is 55.02 ch., the record being 55.09 ch. Distance W to pond edge and stream are 2.00 ch. and 25.25 ch., respectively, the record being 1.50 ch. and 25.70 ch., respectively. Distances N to two swamp edges are 13.05 ch. and 29.40 ch., respectively, compared to 13.00 ch. and 29.50 ch. original record. Found a 1-1/2" O.D. iron pipe purporting to be this corner N84°53.5'W 596.7 ft. from true corner in pond, but it is not supported by any measurements on the ground.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: On 3-21-80, drove a 1" I.D. x 36" iron pipe (no cap) through the ice on the pond and hopefully into a permanently vertical position in the muck bottom of the pond. A 1" I.D. x 36" iron pipe with 4" aluminum cap had, on 9-3-69, been set on a point of upland S0°13'W 3.500 ch. for a Witness Corner. In 1980 the pipe was recovered, but with the cap broken by a falling tree or a bulldozer during timbering operations, and with one of the 1969 witness trees cut down. Witness Corner is now a 1" I.D. x 36" iron pipe with a partial cap, bearing description, remaining on it.

- W. Pine 23 N 9°E (mag.) 18.7 ft. "WC, BT"
- W. Pine 19 N31°W (mag.) 44.3 ft. "WC, NBT"
- W. Birch 9 S 9°E (mag.) 24.5 ft. "WC, NBT"
- Declination 0°20' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1980

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

