

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____ _____ _____
2. Property Controlling in Section	S <u>13</u> T <u>44N</u> R <u>31W</u> S <u>14</u> T <u>44N</u> R <u>31W</u> S _____ T _____ R _____ S _____ T _____ R _____	<u>9</u> <u>16</u> _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 9 02/26/13  
16 05/01/13 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(9-Sec. 13) East 1/16 corner, Section 13. Not previously monumented

(16-Sec. 14) East 1/16 corner between Sections 14 & 23. Not previously monumented.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(9-Sec. 13) Established the position for the corner midway and on a straight line between Center of  
Section 13 1324.89' west and Quarter corner M6 1324.89' east.

(16-Sec. 14) Established the position for the corner midway and on the Section line between Section  
corner 1329.99' east and Quarter corner 1329.99' west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
4" B.Spruce N10°W 5.45' mrkd "1/16S BT"  
7" Tamarack N65°E 16.6' do  
6" B.Spruce S39°E 6.95' do  
4" B.Spruce S78°W 13.55' do  
Set sq'd cedar post adjacent.  
E=7913376.107 N=159225.994

(16) Set 1"IDx11" I.pipe with 4" alum. MDNR cap  
cemented to 5/8"x8" rebar grouted into 3/4"  
dia.x1.5" deep hole in rock.  
Set measuring nail with MDNR tag in the side of:  
4" Spruce N26°E 17.9' mrkd "1/16S BT"  
7" Spruce S43°E 26.45' do  
5" Maple S48°W 10.65' do  
5" Spruce N72°W 18.6' do  
Set sq'd cedar post adjacent.  
E=7911745.154 N=158450.271

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).  
Coord. Ref.=NGS PID RL0202: N= 156159.380 m. E= 7917031.363 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 05/15/2013

For the Michigan Department of Natural Resources, Forest Resources Division

