

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>44N</u> R <u>31W</u>	<u>3</u>
	S <u>14</u> T <u>44N</u> R <u>31W</u>	<u>4</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 04/29/13
4 05/09/13 do hereby state
 that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 24) North 1/16 corner common to Sections 23 & 24. Established in 1997 by the undersigned, midway and on the Section line between Section corner north and Quarter corner south. Set 1"IDx32" I.pipe with 4" alum. MDNR cap. 16" Maple S75E 87.2', 5" Ironwood N60E 105.3', 6" Maple S83W 37.1', squared post adjacent.

(4-Sec. 14) Northwest 1/16 corner, Section 14. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 24) Found the 1997 monument in good condition, at record bearing and distance from the remaining 1997 witness tree Maple S75E, in good condition. Accepted same as a careful and faithful establishment of the position of the corner.

(4-Sec. 14) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Found 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 18" Maple S75°E 87.3' overgrown blazes
 3" Ironwood N81°W 29.05' mrkd "1/16S BT"
 6" Maple N07°W 34.2' do
 3" Maple N38°E 21.8' do
 Set sq'd cedar post adjacent.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap 6" below the surface of a 2-track trail.
 Set measuring nail with MDNR tag in the side of:
 4" Spruce N15°W 18.5' mrkd "1/16S BT"
 5" R.Pine N68°E 29.6' do
 4" R.Pine S14°W 9.35' do
 3" Tamarack N64°W 25.7' do
 E=7910968.308 N=159669.300

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
 Coord. Ref.=NGS PID RL0202: N= 156159.380 m. E= 7917031.363 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/15/2013

For the Michigan Department of Natural Resources, Forest Resources Division

