

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 14 T 44N R 31W	5
	S 14 T 44N R 31W	1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 1 05/13/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 14) North 1/16 corner, Section 14. Not previously monumented.

(1-Sec. 14) West 1/16 corner between Sections 11 and 14. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 14) Established the position for the corner midway and on a straight line between Center of Section 14 1318.29' south and Quarter corner 1318.29' north.

(1-Sec. 14) Established the position for the corner midway and on the Section line between Section corner 1314.10' west and Quarter corner 1314.10' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" Spruce N68°E 16.4' mrkd "1/16S BT"
 4" Poplar S62°E 23.75' do
 4" Poplar S15°W 12.3' do
 11" Spruce N34°W 24.95' do
 Set sq'd cedar post adjacent.
 E=7911368.861 N=159660.660

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" dbl Spruce N32°E 40.95' mrkd "1/16S BT"
 13" Maple S16°E 24.3' do
 9" W.Birch S27°W 14.2' do
 8" Balsam N49°W 12.2' do
 Set sq'd cedar post adjacent.
 E=7910978.165 N=160071.565

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
 Coord. Ref.=NGS PIP RL0202: N= 156159.380 m. E= 7917031.363 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/15/2013

For the Michigan Department of Natural Resources, Forest Resources Division

