

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 31W T 43N R 31W T _____ R _____ T _____ R _____	G-13 ✓ G-1 _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD
99 DEC 30 AM 10:16
L.C. Records: L. 8, P. 41
Graham J. Pisoni
REGISTERED LAND SURVEYOR
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to Sections 33 and 34, T44N, R31W
Section Corner to Sections 4 and 3, T43N, R31W

I, Gary L. Pisoni, in a field survey on April 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by John Burt, U.S. Deputy Surveyor.
Original Corner; Cedar Post
Original Bearing Trees:
Spruce 9" N 57° E 50 lks (33 feet)
Cedar 12" N 49° W 14 lks (9.24 feet)
On June 19, 1849, John Burt, U.S. Deputy Surveyor established the following bearing trees:
Yellow Birch 14" S 42° E 34 lks (22.44 feet)
Cedar 8" S 2 1/2° W 22 lks (14.52 feet)

PEER GROUP APPROVED
Gary L. Pisoni 12-21-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.
On 4/12/99, found a WI/MI Power Co. brass cap encased in concrete, stamped as follows: WMP Co., T44N, R31W, S-33, S-34, S-4, S-3, T43N, and located at a fence corner, at the edge of a swamp. Concrete monument has been used for many surveys throughout the area. I accept the monument as the best available evidence for restoring the corner position.
Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument, I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)
Balsam 11" N 77° W 7.94 feet
Red Maple 7" S 69° E 17.57 feet
Cedar 7" S 16° E 35.08 feet
Red Maple 8" S 17° W 48.74 feet
Steel sign post North 1.47 feet

99-41
Signed by *Gary L. Pisoni* Date 12-28-99
Surveyor's Michigan License No. 27457

