

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 1 T 44N R 31W	3
	S 1 T 44N R 31W	1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 05/04/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(3-Sec.1) North 1/16 corner between Sections 1 and 2. 1997 - Established by the undersigned on the Section line between Quarter corner 1324.53' south and Section corner 1350.36' north. Set 1"ID I.pipe with 4" alum. MDNR cap. 5" W.Spruce N54E 23.6', 4" W.Spruce S48E 9.7', 3" W.Spruce N83W 11.3', 6" W.Spruce N14W 3.5'.

(1-Sec. 1) West 1/16 corner between Section 1, T44N-R31W and Section 36, T45N-R31W. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(3-Sec. 1) Recovered the 1997 monument in good condition, at the proper position, and at record bearing from the 1997 witness trees. The Spruce NE is dead and down. The remaining three are in good condition. I note that the distances to these trees are transposed on the 1997 record and they are corrected below. Accepted the monument as a careful and faithful establishment of the position of the corner.

(1-Sec. 1) Established the corner midway and on the township line between Quarter corner 1319.71' east and Section corner 1319.71' west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(3) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Spruce S47E 11.5' old blazes 1997 BT  
 5" Spruce N82W 3.6' do do  
 7" Spruce N13W 23.5' do do  
 7" Spruce N14E 19.8' mrkd "S1/16 BT"  
 Sq'd post adjacent. Bearings are magnetic.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" W.Spruce N20E 4.6' mrkd "1/16S BT"  
 9" J.Pine N73E 8.3' do  
 7" W.Spruce S19E 4.9' do  
 5" W.Spruce S52W 9.9' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 06/07/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division