

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>1</u> T <u>44N</u> R <u>31W</u>	_____	<u>4</u>
	S <u>1</u> T <u>44N</u> R <u>31W</u>	_____	<u>5</u>
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2			1	
3													
4	7		8		9		10		11			12	
5													
6	18		17		16		15		14			13	
7													
8	19		20		21		22		23			24	
9													
10	30		29		28		27		26			25	
11													
12	31		32		33		34		35			36	
13													

I, Stephan J. Szyszkoski, in a field survey on 4 05/04/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 1) Northwest 1/16 corner, Section 1. Not established in the original survey.

(5-Sec. 1) North 1/16 corner, Section 1. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 1) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, I found a 1/2" dia. uncapped iron rod, not of record, S11E 1.8' distant.

(5-Sec. 1) Established the corner on a straight line between Quarter corner 1355.37' north and the intersection of 1/4 lines of Section 1 1321.03' south, being 20.00 chains, proportionate to the dimensions derived from the original U.S. plat of this township, north of the Center of the Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 9" B.Spruce N18E 15.0' mrkd "1/16S BT"
 6" B.Spruce N79E 23.5' do
 10" B.Spruce S86W 17.6' do
 5" B.Spruce N50W 15.1' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 6" Balsam N20E 13.0' mrkd "1/16S BT"
 9" Balsam S83E 15.9' do
 4" B.Spruce S66W 20.7' do
 6" W.Spruce N32W 7.0' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/07/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division