

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	A9
	T 44N R 31W	A7
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on A9 05/29/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:**
- (A9) Corner common to Sections 19-30 T44N-R31W and Sections 24-25 T44N-R32W. 2002 - Corner approved by Iron Co. Peer Group and recorded in Liber 9 LCR Page 317 by G.L.Pisoni PS. Found Wisconsin Michigan Power Company concrete monument with 3" square brass tablet. White Pine 18" S49E 95.89', White Pine 36" N61E 91.26', White Pine 22" N80W 101.61', Aspen 6" S39W 9.11', Steel sign post North 0.80'.
- (A7) Corner common to Sections 18-19 T44N-R31W and Sections 13-24 T44N-R32W. 2003 - Corner monument approved by Iron Co. Peer Group and recorded in Liber 10 L.C.R. Page 147 by G.L.Pisoni PS. Found Wisconsin Michigan Power Company concrete monument with 3" square brass tablet. Cedar 12" N45E 26.73', Cedar 12" S20E 4.51', Cedar 12" S85W 13.82', B.Spruce 6" S69E 48.34', steel sign post N83W 0.80'.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
- (A9) Found the WMPCO monument as described, in good condition and at record bearing and distance from the 2002 witnesses. The W.Pine NBTs are in good condition. The Aspen NBT SW is dead and down. Marked an additional witness tree, as described below.
- (A7) Found the WMPCO monument of record, as described, in good condition and at record bearing and distance from the 2003 witnesses of record, all in good condition. The Cedar NBT S20E was cut down to facilitate GPS observations. Left the monument in place and marked one new witness tree as described below.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- (A9) Fd. WMPCO concrete monument with 3" brass cap. The W.Pine NBTs of record are in place and in good condition. Set measuring nail with MDNR tag in the side of:
 10" Maple in clump S84E 91.8' mrkd "S30 NBT"
 The steel sign post of record was found at record bearing and distance. Bearing to Maple NBT is magnetic.
- (A7) Fd. WMPCO concrete monument with 3" sq. brass tablet. The 2003 witnesses of record (exception noted above) are in place and in good condition. Set measuring nail with MDNR tag in the side of:
 10" Cedar S20E 8.05' mrkd "S19 NBT"
 Bearing is magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/19/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities

16070
 16073