

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	B7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 19 T 44N R 31W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7		●											
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on B7 05/29/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (B7) Quarter corner common to Sections 18 and 19. 2003 - Monumented with a witness corner 516.84' N89 53'47"W of the corner position by G.L.Pisoni PS. Corner approved by Iron County Peer Group 12/19/03 and recorded in Liber 10 Page 149, Iron County Land Corner Records. Set 5/8"x30" rebar with 3" dia. alum. cap. Spruce 12" N69E 64.27', Spruce 10" S71W 45.21', Tamarack 12" N12W 19.71', Spruce 5" N25E 25.45', Steel sign post S15E 0.50'.

(5-Sec. 19) North 1/16 corner, Section 19. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (B7) Recovered the 2003 witness corner monument in good condition and at record bearing and distance from the 2003 witnesses. The 12" Spruce NE is standing dead, the 5" Spruce NE is dead and down. The remaining two 2003 witness trees are in good condition, blazed and scribed. Left the monument in place and made two new witnesses as described below.

(5-Sec. 19) Established the corner midway and on a straight line between Quarter corner 1321.35' north and intersection of quarter lines 1321.35' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (B7) Found Iron County monument with 3" dia. alum. cap for a witness corner. Set measuring nail with MDNR tag in the side of:
 9" Balsam S87W 18.8' mrkd "WC BT"
 7" Cherry N59W 18.6' do
 Found nail in the witness trees of record:
 10" Spruce S73W 45.2'
 12" Tamarack N10W 19.7'
 Fd. steel sign post adjacent. Bearings magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Spruce S13E 62.8' mrkd "1/16S BT"
 3" Spruce S22W 50.4' do
 4" Poplar N13E 22.0' do
 5" Poplar S59E 12.65' do
 Set sq'd post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/19/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities