

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 36 T 44N R 31W	13
	S 36 T 44N R 31W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

07/23/2008

I, Stephan J. Szyszkoski, in a field survey on 07/23/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(13-Sec. 36) Southeast 1/16 corner, Section 36. Not established in the original survey.

(12-Sec. 36) South 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(12-Sec. 36) Established the corner midway and on a straight line between Center of Section 1318.67' north and Quarter corner 1318.67' south. From the position for the corner, the center of Channing Rd is S41W 24.3' distant (measured on a perpendicular to the road).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Cherry N01W 22.45' mrkd "1/16S BT"
 9" Maple S77E 28.4' do
 17" Maple S05E 35.85' do
 3" Balsam S52W 15.0' do
 Set sq'd post adjacent. Bearings magnetic.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Spruce N37W 32.55' mrkd "1/16S BT"
 6" Maple N23W 17.35' do
 8" Maple N89E 22.6' do
 18" Spruce S60E 41.25' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities

16112

16113