

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	M12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T 36 R 44N R 31W	L12
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

M12 07/16/2008

L12 07/23/2008

I, Stephan J. Szyszkoski, in a field survey on _____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35				
13													

A. Description of original monument and accessories and/or subsequent restoration:

(M12) Quarter corner common to Section 36 T44N-R31W and Section 31 T44N-R30W. 2003 - Remonumented by G.L.Pisoni RLS. Approved by Iron Co. Peer Group Dec. 19, 2003 and recorded in L 10, Page 221, Iron County Records. Set 5/8" diameter x 30" rebar with Iron County Remonumentation cap. White Birch 11" S19W 24.37' (1963 NBT), Sugar Maple 9" N50W 36.51', Balsam 5" N37W 9.55', Sugar Maple 6" N21E 49.57', White Birch 15" N72E 1.90', Steel sign post S63W 0.90'.

(L12) Center of Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M12) Found the 2003 monument in good condition and at record bearing and distance from the witness trees of record, all in good condition but for the Balsam NW which is now standing dead. Marked a new bearing tree as described below.

(L12) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M12) Fd. 5/8" rebar with Iron County cap.
 Set measuring nail with MDNR tag in the side of:
 13" Sugar N23W 35.6' mrkd "1/4S NBT"
 10" W.Birch S21W 24.4' "S36" 1963 NBT
 Fd. nail in
 16" W.Birch N67E 1.9' mrkd "X BT"
 9" Sugar N46W 36.5' do
 13" Sugar N23W 35.6' do
 Steel sign post S63W 0.9'
 Bearings are magnetic.

(L12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" Balsam N16W 26.7' mrkd "C1/4 BT"
 8" Balsam N44E 24.45' do
 4" Tamarack S37W 37.25' do
 4" Spruce N88W 22.1' do
 Set sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

