

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>36</u> T <u>44N</u> R <u>31W</u>	<u>16</u>
	S <u>23</u> T <u>44N</u> R <u>31W</u>	<u>J8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

16 07/23/2008

I, Stephan J. Szyszkoski, in a field survey on J8 07/10/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		●		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													●

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 36) East 1/16 corner between Sec. 36 T44N-R31W and Section 1 T43N-R31W. 1988 - Established by K.L.Sackett RLS midway and on the Township line between Quarter corner to west and Township corner to east. Set 1"IDx32" I.pipe with 4" aluminum cap. 4" Spruce West 0.5', squared, 3" Spruce N03E 1.5', 4" Spruce S22E 11.0', 5" Spruce N75W 9.7'.

(J8) Center of Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 36) The 1988 monument was recovered in good condition and at record bearing and distance from the 1988 witnesses. The Spruce S22E is dead and down. The squared spruce west 0.5' was cut down to facilitate GPS observations (left 4' high stub). The monument was found to be substantially at the midpoint between Quarter corner to west and Township corner to east and I accept same as a careful and faithful determination of the position of the corner.

(J8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Spruce N73W 10.1' old marks 1988 BT
 5" Spruce N06E 1.8' do do
 6" Spruce S58E 14.9' mrkd "1/16S BT"
 6" Spruce S34E 12.8' do do
 Bearings are magnetic.

(J8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" R.Pine N85E 22.9' mrkd "C1/4 BT"
 7" R.Pine S77E 12.7' do do
 4" Spruce S84W 8.7' do do
 9" J.Pine N07W 8.3' do do
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

