

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	K11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 34 T 44N R 31W	1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

K11 07/15/2008

I, Stephan J. Szyszkoski, in a field survey on 1 07/07/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (K11) Corner common to Sections 25-26-35-36. 2003 - Approved by Iron County Remonumentation Program. Gary L. Pisoni RLS set a witness monument, a 5/8" diameter by 30" long rebar, with 3" alum. Iron County cap, 89.06' easterly from the corner monument of record. Rec. in Liber 10 Page 206, Iron County Records. 2003 witnesses: 9" Balsam N12E 15.90', 11" Spruce S59E 11.15', 8" Spruce S11E 20.62', 10" Balsam N36W 22.28', Steel sign post East 0.60'.

(1-Sec. 34) West 1/16 corner between Sections 27 and 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K11) Found the witness monument of record, in good condition, and at record bearing and distance from the 2003 witness Balsam NE, both Spruces SE, in good condition, and the steel sign post. Left the monument in place and made a new witness as described below.

(1-Sec. 34) Established the corner midway and on the Section line between Section corner (location marked by witness corner of record) 1323.47' west and Quarter corner 1323.47' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K11) Found Iron County Monument witness corner 89.06' easterly of the corner position. Set measuring nail with MDNR tag in:
 7" Spruce N42W 19.95' mrkd "WC BT"
 Found existing witnesses:
 8" Balsam N16E 15.90' mrkd "X BT"
 10" Spruce S60E 11.15' do
 7" Spruce S08E 20.62' do
 steel sign post East 0.6' Bearings magnetic.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 12" Sugar N10E 20.8' mrkd "1/16S BT"
 11" Sugar S20E 18.9' do
 10" Sugar S41W 7.2' do
 6" Sugar N15W 11.6' do
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

