

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 25 T 44N R 31W	16
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 09/10/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 25) East 1/16 corner between Sections 25 and 36. 1988 - Established by K.L.Sackett RLS midway and on line between Section and Quarter corner. Set 1"IDx32" I.pipe with 4" aluminum cap. 10" Spruce S28E 7.8', 8" Spruce S65W 6.2', 8" Spruce N61E 4.8', 8" Spruce S25W 2.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 25) Recovered the 1988 monument, in good condition and at record bearing and distance from the Spruce BT S65W 6.2', now a stump with scribing visible. The remaining 1988 BTs were not recovered. Verified the position of the monument with respect to Section corner 1321.35' east and Quarter corner 1321.28' west and accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 8" B.Spruce N82E 18.8' mrkd "1/16S BT"
 5" Tamarack S59E 17.5' do
 5" B.Spruce S14W 11.2' do
 11" W.Pine N50W 28.9' do
 Set sq'd post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski Date 09/15/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities