

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45 N R 32 W

DESCRIPTION OF CORNER 1/4 corner between Sections 3 and 34

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 11, 1968

WITNESSES TO CORNER..... White Spruce 6 N47°E 55 lks. "1/4 S NBT"



White Spruce 6 S85°W 90 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner set by proportionate measurement on line between an original section corner 39.995 chains west and a probable original section corner 119.985 chains east. Found no identifiable evidence of the original corner or its accessories or of a replacement monument or its accessories. From the place where this corner was set there is a badly rotted W. Pine stump corresponding in size to one of the original BT's and at the record bearing, but only 92 links from the corner rather than the 102 links record distance. Could not identify this stump as being the original BT, so placed the corner by proportionate measurements.

Corner lies in a small, circular, open, wet pot-hole about 1/4 acre in size.

Variation at this corner is about 1° 45' West.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 2/14/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68