

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45 N R 32 W

DESCRIPTION OF CORNER West 1/16 corner between Sections 3 and 34

CORNER MONUMENT 1" I.D.x36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 11, 1968

WITNESSES TO CORNER..... Sugar Maple 5 S7°W 13½ lks. "1/16 S BT"



Sugar Maple 6 S61½°E 10 lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established midway on line between an original section corner about 20 chains west and 1/4 corner about 20 chains east, previously established by proportionate measurements.

Found a squared cedar post bearing S6½°E 15½ links from the corner here established, set in recent times by unknown persons. No marks on post and no visible witnesses.

Corner lies about 15 links east of a N & S woods road and agrees fairly well with swamp edges to east and west mentioned in original field notes.

Variation at this corner is about 1° 45' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Arthur O. Enger DATE 2/14/69
REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing