

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


Iron COUNTY
T 44-45N R 32 W

DESCRIPTION OF CORNER 1/4 corner between Sections 2 and 35

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 11, 1968

WITNESSES TO CORNER..... Cedar 12 N9°W 27½ lks. "1/4 S NBT"



Cedar 12 West 14½ lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner set by proportionate measurement on line between a probable original section corner 39.995 chains East and an original section corner 119.985 chains West. Found no evidence of the original corner or its accessories or of any replacement monument or accessories.

Found a Northern Paper Mills location poster on a Cedar 12 N9°W 27½ lks. from corner, with a tack at the S1/4 corner of Sec. 35, T45N, R32W, and bearing the notation "About 1/4. BGB 8/13/42".

Position checks fairly well with original field note call to a swamp edge to the east and a stream crossing to the west.

Variation at this corner is about 1° 45' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

2/14/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68