

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44-45 N.R. 32 W


Iron COUNTY

DESCRIPTION OF CORNER E 1/16 corner between Sec. 4 & 33

CORNER MONUMENT 1" I.D. by 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 13, 1968

WITNESSES TO CORNER..... Sugar Maple 14 N23W 27½ lks. "1/16 S BT"



Sugar Maple 8 S27W 34 lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

## DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner placed midway on line between NE Sec. Cor. (original evidence present) and N ¼ corner of Sec. 4 which had been previously set by proportionate measurements (no original evidence). From this corner, distance east to Sec. Cor. is 20.01 chains and west to ¼ cor. is 20.01 chains.

Corner monument is against south side of a large gray rock about 2½ ft. by 3 ft. in horizontal size.

A temporary 20.00 chain stake had been set several years ago about 21 links southerly of the corner established here.

SURVEYOR'S SEAL

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR

DATE

9/4/68