

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44-45 N.R. 32 W


Iron COUNTY

DESCRIPTION OF CORNER W 1/16 corner between Sec. 4 & 33

CORNER MONUMENT 1" I.D. by 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 13, 1968

WITNESSES TO CORNER..... Yellow Birch 14 S54E 10 $\frac{1}{2}$ lks. "1/16 S BT"



Balsam Fir 6 S80W 17 $\frac{1}{2}$ lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner placed midway on line between NW section corner (original BT present) and N $\frac{1}{4}$ corner of Sec. 4 which had been set previously by proportionate measurements (no original evidence). From this corner, distance west to Sec. Cor. is 20.01 chains and east to $\frac{1}{4}$ cor. is 20.01 chains.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

9/4/68