

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>32</u> E. W.	<u>I9</u>
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	T. <u>44</u> N. R. <u>32</u> E. W.	<u>14, 7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 8, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 19:** Original monument and accessories not found. Found Wisconsin Power Co. Mon.
- Corner 14:** Not set on original survey nor subsequently apparently
- Corner 7:** Not set on original survey nor subsequently apparently
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 19:** Restored at monument
- Corner 14:** Established midway and on line between section corner south and $\frac{1}{4}$ corner north
- Corner 7:** Established midway and on line between section corner north and $\frac{1}{4}$ corner south
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner 19:** Wisconsin Power Company Monument. 4" balsam N77E 2.3' S23, NBT
5" spruce N27W 22.3' S22, NBT
- Corner 14:** Set 1" I.D. by 32" I.P. with 4" aluminum cap. 8" maple S34E 26.6' 1/16S, BT
6" maple S68W 41.3' 1/16S, BT
16" w. pine N39W 12.4' 1/16S, BT
- Corner 7:** Set 1" I.D. by 32" I.P. with 4" aluminum cap. 5" maple S19E 5.5' 1/16S, BT
5" sugar S38W 3.8' 1/16S, BT
12" sugar N37E 12.4' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-29-85

CHIEF OF SURVEY ARTS
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006