

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**Iron County**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>32</u> W.	<u>G12</u>
2. PROPERTY CONTROLLING IN SECTION <u>33</u>	T. <u>44</u> N. R. <u>32</u> W.	<u>7, 14, 10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 7, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**Corner G12: Original monument and accessories not found.**

**Corner 7: Not set on original survey nor subsequently apparently.**

**Corner 14: Not set on original survey nor subsequently apparently.**

**Corner 10: Not set on original survey nor subsequently apparently.**

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**Corner G12: Restored midway and on line between corners north and south.**

**Corner 7: Established midway and on line between section corner north and 1/4 corner south**

**Corner 14: Established midway and on line between section corner south and 1/4 corner north**

**Corner 10: Established on line between corners north and south.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner G12: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 5" sugar S05W 35.7' 1/4 S, NB  
 4" sugar N89E 17.3' 1/4 S, NB  
 4" maple S86W 5.3' 1/4 S, NB**

**Corner 7: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 9" aspen S42W 11.3' 1/16 S, B  
 5" aspen S24E 13.5' 1/16 S, B**

**Corner 14: Set 1" I.D. by 32" I.P. with 4" aluminum cap.  
 4" balsam N07W 23.0' 1/16 S, BT  
 5" balsam S31W 61.5' 1/16 S, BT**

**Corner 10: Set 1" I.D. by 64" I.P. with 4" aluminum cap.  
 7" cedar N70W 52.1' 1/16 S, BT  
 12" tan N30E 87.5' 1/16 S, BT**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-6-85  
 CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 25, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET