

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Iron County FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>44</u> N. <u>26</u> S., R. <u>32</u> E. <u>W.</u>	<u>G9, H7</u>
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	T. <u>44</u> N. <u>26</u> S., R. <u>32</u> E. <u>W.</u>	<u>2, 3</u>
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 4, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G9: Original monument and accessories not found. Found Wisconsin-Michigan Power Company monument.**
- Corner H7: Original monument and accessories not found. Found approximate pipe.**
- Corner 2: Not set on original survey. Found approximate pipe.**
- Corner 3: Not set on original survey. Found approximate pipe. S51W 15.9'**
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G9: Restored at Wisconsin-Michigan Power Company Monument.**
- Corner H7: Restored midway and on line between section corners east and west.**
- Corner 2: Established midway and on line between 1/4 corner west and section corner east.**
- Corner 3: Established midway and on line between 1/4 corner south and section corner north**
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G9: Wisconsin-Michigan Power Company Monument. 12" red pine S04W 12.3' S28,NE
12" red pine N20E 74.3' S22,NE**
- Corner H7: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 6" maple N04E 8.1' 1/8S, NBT
12" maple S22E 20.7' 1/8S, NBT
7" maple N52W 23.8' 1/8S, NBT**
- Corner 2: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 6" hemlock N48E 20.9' 1/16S, BT
12" maple S30W 33.9' 1/16S, BT
5" maple squared S12W 1.8'**
- Corner 3: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 8" spruce S36W 20.2' 1/16S, BT
6" maple N64W 34.1' 1/16S, BT**

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-29-85

MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006