

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**Iren County**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. R. <u>32</u> W.	<u>I7, I8, G13</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 8, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner I7:** Original monument and accessories not found. Found old L.E.S. Post which has been used as corner for many years.
- Corner I8:** Original monument and accessories not found. Found Champion location poster on hemlock S67E 13.5'
- Corner G13:** Found original bearing tree cedar 14" N48E 24 links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner I7:** Restored at L.E.S. Post fits good with other corner in area.
- Corner I8:** Restored midway and on line between corners north and south
- Corner G13:** Restored from cedar bearing tree.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Corner I7:** Set 1" I.D. by 32" I.P. with 4" aluminum cap. 8" sugar S89E 15.9' S23, NBT  
 7" cedar S67W 11.1' S22, NBT  
 12" cedar N58E 47.8' S14, NBT
- Corner I8:** Set 1" I.D. by 32" I.P. with 4" aluminum cap. 12" sugar N62W 17.9' 1/4 S, NBT  
 10" sugar N37E 20.2' 1/4 S, NBT  
 6" sugar S07E 21.4' 1/4 S, NBT
- Corner G13:** Set 1" I.D. by 32" I.P. with 4" aluminum cap. 12" sugar S80E 12.3' S3, NBT  
 8" sugar N02W 12.5' S33, NBT  
 10" sugar S70W 25.8' S4, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 12-29-85

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006