

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>32</u> W.	<u>E8</u>
2. PROPERTY CONTROLLING IN SECTION <u>21</u>	T. <u>44</u> N. R. <u>32</u> W.	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 13, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner E8: Original monument and accessories not found.

Corner 3: Not set on original survey; Found approximate pipe N69E 15.9'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner E8: Restored midway and on line between corners north and south.

Corner 3: Established midway and on line between section corner north and 1/4 corner south

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner E8: Set 1" I.D. by 32" I.P. with 4" aluminum cap.

5" maple N76E 30.8' 1/8S, MBT
 4" maple S70E 24.6' 1/8S, MBT

Corner 3: Set 1" I.D. by 32" I.P. with 4" aluminum cap.

7" w. birch S50E 55.0' 1/16S, BT
 8" aspen N42W 15.2' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-29-85

CHIEF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET