

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Iron

Located In:	Corner Code #
1 Public Land Survey T 44N R 32W	14
T R	15
T R	
T R	
2 Property Controlling in Section S 11 T R	3
S 11 T R	10
3 Miscellaneous Property in Sec S T R	
S T R	

*13*  
*14*  
*15*

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith Sackett, in a field survey on April 26, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A Description of original monument and accessories and/or subsequent restoration:

14	15	3	10
Original monument and accessories not found. Fits good with swamp edge north.	Original monument and accessories not found, possible line tree south.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

14	15	3	10
Restored midway and on line.	Restored from line tree south, section corners east and west and north.	Established midway and on line.	Established midway and on line.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

14	15	3	10
Set 1" I.B. by 36" I.P. with 4" aluminum cap.	Set 1" I.B. by 36" I.P. with 4" aluminum cap.	Set 1" I.B. by 32" I.P. with 4" aluminum cap.	Set 1" I.B. by 32" I.P. with 4" aluminum cap.
6" spruce S60E 32.6' 1/4S, NBT 28" white pine N42E 48.0' 1/4S, NBT 26" white pine N75W 26.6' 1/4S, NBT	6" balsam S72E 15.0' S14, NBT 9" white birch S67W 28.9' S15, NBT 8" balsam N48E 18.8' S11, NBT	8" balsam N08E 60.3' 1/16S, BT 16" white birch S88E 53.2' 1/16S, BT 8" tamarack S42W 123.4' 1/16S, BT	7" spruce S68W 18.6' 1/16S, BT 8" balsam S30W 14.8' 1/16S, BT 6" spruce S54E 34.9' 1/16S, BT

Signed by Keith Sackett Date 9/11/89

Surveyor's Michigan License No. 19006