

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
IrDA
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>44N</u> R <u>R32W</u>	<u>H3</u>
	T _____ R _____	<u>J3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>11</u> T _____ R _____	<u>1</u>
	S _____ T _____ R _____	<u>2</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Beckett, in a field survey on April 24, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

A. Description of original monument and accessories and/or subsequent restoration:

<u>H3</u>	<u>J3</u>	<u>1</u>	<u>2</u>
Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>H3</u>	<u>J3</u>	<u>1</u>	<u>2</u>
Restored midway and on line.	Restored midway and on line.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>H3</u>	<u>J3</u>	<u>1</u>	<u>2</u>
Set 1" I.D. by 32" I.P. with 4" aluminum cap.	Set 1" I.D. by 34" I.P. with 4" aluminum cap.	Set 1" I.D. by 34" I.P. with 4" aluminum cap.	Set 1" I.D. by 36" I.P. with 4" aluminum cap.
12" tanarack N04W 13.8' 1/4S, NBT	12" white pine S50E 7.8' 1/4S, NBT	6" spruce N60W 20.7' 1/16S, BT	12" sugar S42N 19.6' 1/16S, BT
3" balsam S50W 18.1' 1/4S, NBT	10" white pine N30W 51.8' 1/4S, NBT	7" tanarack S10W 37.8' 1/16S, BT	14" ash N30E 37.8' 1/16S, BT
3" balsam S40E 13.6' 1/4S, NBT	8" spruce N45E 1/4S, NBT	7" spruce N75E 49.6' 1/16S, BT	9" cherry S28W 5.5' with location poster.
3" balsam S40E 13.6' 1/4S, NBT			
3" balsam post square 5' long.			

Signed by Keith Beckett Date 5/12/89

Surveyor's Michigan License No. 19066

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983