

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 32W	K3
	T _____ R _____	L3
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S 12 T _____ R _____	1
	S _____ T _____ R _____	3
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	

ad

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

I, Keith Sackett, in a field survey on April 24, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K3	L3	1	3
Original monument and accessories not found. Found 1" I.I. iron pipe by unknown length set by unknown person, fits good with other corners and land calls.	Original monument and accessories not found. Found iron pipe set by unknown person that fits good between corners east and west.	Not set on original survey. Found pipe set by unknown person which appears to have been used as corner. It is five feet east of midway between corners.	Not set on original survey. Found 1 1/2" iron pipe that fits well with corners north and south. No information on who set pipe. Pipe is 5.0' east of midway on line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K3	L3	1	3
Restored at iron pipe.	Restored at 1 1/2" iron pipe.	Established at iron pipe.	Established at iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K3	L3	1	3
1" I.D. by unknown length	1 1/2" I.D. I.P. by unknown length.	1 1/2" I.P. by unknown length	1 1/2" I.P. by unknown length
4" maple 874N 18.0' B11, NBT	5" maple 889E 16.0' 1/4B, NBT	14" yellow birch N32N 9.0' 1/16B, BT	15" cedar 840E 21.7' 1/16B, BT
7" balsam 810E 39.0' 812, NBT	4" maple N48E 20.8' 1/4B, NBT	9" maple 866N 13.0' 1/16B, BT	5" balsam N16W 35.0' 1/16B, BT
2" maple N89E 43.0' B1, NBT	6" maple N46N 6.9' 1/4B, NBT	9" maple 874E 7.7' 1/16B, BT	6" balsam 840W 35.8' 1/16B, BT
	8" white birch N50W 7.0' with location poster.		

Signed by Keith Sackett Date 5/12/89

Surveyor's Michigan License No. _____ 19008

