

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Iron

County	Located In:	Corner Code <del>##</del>
1. Public Land Survey	T 44N R32N	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 11 T R	15
	S T R	14
3. Miscellaneous Property in Sec	S 12 T R	15
	S 13 T R	15

*fw*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on June 12, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>11-15</u>	<u>16</u>	<u>12-15</u>	<u>13-15</u>
Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>11-15</u>	<u>16</u>	<u>12-15</u>	<u>13-15</u>
Established midway and on line.	Established midway and on line.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>11-15</u>	<u>16</u>	<u>12-15</u>	<u>13-15</u>
Set 1" ID x 32" IP with 4" aluminum cap.	Set 1" ID x 32" IP with plastic cap.	Set 1" ID x 32" IP with 4" aluminum cap.	Set 1" ID x 32" IP with 4" aluminum cap.
7" spruce S10E 9.8' 1/168 BT	5" spruce S12W 5.9' 1/168 BT	6" balsam N60W 9.9' 1/168 BT	7" sugar S50E 5.3' 1/168 BT
14" spruce N41E 28.0' 1/168 BT	3" spruce S72E 10.5' 1/168 BT	7" spruce N63E 39.1' 1/168 BT	12" sugar N64E 12.4' 1/168 BT
16" red pine N01W 29.7' 1/168 BT	2" tamarack N01E 18.5' 1/168 BT	4" spruce S25E 28.6' 1/168 BT	9" sugar N26W 8.8' 1/168 BT

Signed by Keith S. Sackett

Date 9-21-89

Surveyor's Michigan License No. 19004

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

