

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Irma  
(County)

Located in:

Corner Code ##

1. Public Land Survey	T <u>44N</u> R <u>R32W</u>	<u>K7</u>
	T _____ R _____	<u>K8</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S <u>12</u> T _____ R _____	<u>10</u>
	S <u>13</u> T _____ R _____	<u>10</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on June 7, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	28	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>K7</u>	<u>K8</u>	<u>10</u>	<u>10</u>
Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>K7</u>	<u>K8</u>	<u>10</u>	<u>10</u>
Restored midway and on line.	Restored midway and on line.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K7</u>	<u>K8</u>	<u>12-10</u>	<u>13-10</u>
Set 1" ID x 32" IP with 4" aluminum cap.	10" spruce S40E 8.9' 1/48 NBT	Set 1" x 36" IP with 4" aluminum cap.	Set 1" ID x 36" IP with 4" aluminum cap.
12" spruce N40E 11.1' 8/13 NBT	10" spruce S20E 21.8' 1/48 NBT	8" spruce N50W 6.8' 1/168 BT	Corner falls in beaver dam.
3" spruce S33E 16.9' 8/24 NBT	10" cherry S42W 26.8' 1/48 NBT	6" spruce S27W 19.4' 1/168 BT	8" spruce S45E 86.8' 1/168 BT
	12" spruce S30E 3.2' squared	7" spruce N54E 16.5' 1/168 BT	10" ironact S58E 92.5' 1/168 BT

Signed by Keith Sackett Date 9-21-89

Surveyor's Michigan License No. 17006

