

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

| Iron                               | Located in:             | Corner Code # |
|------------------------------------|-------------------------|---------------|
| (County)                           |                         |               |
| 1. Public Land Survey              | T 44N R 22E             | 13            |
|                                    | T _____ R _____         | KS            |
|                                    | T _____ R _____         | K6            |
|                                    | T _____ R _____         |               |
| 2. Property Controlling in Section | S 13 T _____ R _____    | 3             |
|                                    | S _____ T _____ R _____ |               |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ |               |
|                                    | S _____ T _____ R _____ |               |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 3  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 4  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 5  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 6  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 7  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 8  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 9  |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 10 |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 11 |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 12 |   |   |   |   |   |   |   |   |   |   |   |   |   |
| 13 |   |   |   |   |   |   |   |   |   |   |   |   |   |

I, Keith Sackett, in a field survey on June 14, 1988, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| 13  | KS   | K6   | 3  |
|---|--|--|--|
| Original monument and accessories not found. Found location of old pipe by unknown person fits good within other corners in area. | Original monument and accessories not found. | Original monument and accessories not found. | Not set on original survey nor subsequently, apparently. |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| 13                         | KS                             | K6                           | 3                               |
|----------------------------|--------------------------------|------------------------------|---------------------------------|
| Restored at pipe location. | Restored by double proportion. | Restored midway and on line. | Established midway and on line. |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| 13                                     | KS                                     | K6                                     | 3                                      |
|--|--|--|--|
| Set 1" x 3/8" IP with 4" aluminum cap. | Set 1" x 3/8" IP with 4" aluminum cap. | Set 1" x 3/8" IP with 4" aluminum cap. | Set 1" x 3/8" IP with 4" aluminum cap. |
| 16" spruce N75E 10.9' BS NBT           | 9" balsam S54E 12.0' B13 NBT           | 9" spruce N62W 4.6' 1/48 NBT           | 3" sugar N18E 4.4' 1/168 BT            |
| 4" spruce N64W 11.1' BS NBT            | 8" balsam S44E 35.3' B14 NBT           | 7" spruce N22E 6.9' 1/48 NBT           | 4" sugar S69W 8.6' 1/168 BT            |
| 9" spruce S32W 22.0' S6W NBT           | 28" white pine N01W 61.5' B11 NBT      | 7" spruce S36E 17.4' 1/48 NBT          | 12" sugar S36E 26.7' 1/168 BT          |

Signed by Keith Sackett Date 9-21-88

Surveyor's Michigan License No. \_\_\_\_\_ 19006

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 26, 1971

REVISED MAY 14, 1975  
 REVISED JAN., 1980

