

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron
 (County)

	Located in:	Corner Code 79
1. Public Land Survey	T <u>44</u> R <u>32</u>	<u>G7</u>
	T _____ R _____	<u>R9</u>
	T _____ R _____	<u>L7</u>
2. Property Controlling in Section	S <u>12</u> T _____ R _____	<u>16</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on May 23, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>G7</u>	<u>R9</u>	<u>L7</u>	<u>16</u>
Original monument and accessories not found. Found <u>"T" iron that fits reasonably good with other corners in area.</u>	Original monument and accessories not found. Found <u>Wisc.-Rich. Power Co. monument.</u>	Original monument and accessories not found. Found <u>WI-WI Power Co. monument.</u>	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>G7</u>	<u>R9</u>	<u>L7</u>	<u>16</u>
Restored at <u>"T" iron.</u>	Restored at <u>WI-WI Power Co. monument.</u>	Restored at <u>WI-WI Power Co. monument.</u>	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>G7</u>	<u>R9</u>	<u>L7</u>	<u>16</u>
Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap in marsh.
9" poplar N44W 14.2' S16 NBT	18" v. pine S82W 57.8' S26 NBT	12" spruce N22W 14.5' 1/4s NBT	4" tamarack N78W 77.3' 1/16s BT
6" maple S17W 11.1' S21 NBT	24" r. pine N48E 39.8' S24 NBT	10" spruce S69W 8.0' 1/4s NBT	4" tamarack N53W 82.7' 1/16s BT
5" maple S46E 6.1' S22 NBT	10" v. pine S76E 53.7' S25 NBT	12" balsam S12E 23.0' 1/4s NBT	

Signed by Keith Sackett Date _____
 Surveyor's Michigan License No. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983

