

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>32</u> X. X. R. <u>32</u> W.	B11, C11
2. PROPERTY CONTROLLING IN SECTION <u>30</u>	T. <u>44</u> N. <u>32</u> X. X. R. <u>32</u> W.	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-28, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner C11: Original monument and accessories not found
- Corner B11: Original monument not found. Found old pine stump bottom which fits for bearing and distance. Also found old cedar stump which fits for line tree west.
- Corner 16: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner C11: Restored corner from land calls. North - south - east and Section corner west.
- Corner B11: Restored corner from old pine stump. Location fits with corners east and west and possible line tree west.
- Corner 16: Established midway and on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>Corner C11: Set 1" ID by 32" iron pipe with 4" alum. cap. Sugar N09W 5.1 ft S30, NBT Sugar S86E 8.3 ft S32, NBT Sugar S41W 7.3 ft S31, NBT Sugar Squared S46W 2.6 ft</p>	<p>Corner B11: Set 1" ID by 32" Iron pipe with 4" alum. cap 9" Sugar N52W 40.1 ft 1/4S, NBT 10" W.Birch N14E 23.2 ft 1/4S, NBT 6" W.Birch S30W 15.6 ft 1/4S, NBT</p>	<p>Corner 16: Set 1" ID By 32" Iron pipe with 4" alum. cap 10" cedar S61W 37.3 ft 1/16S, BT 6" Sugar N43E 31.7 ft 1/16S, BT 9" Y.Birch S72E 5.6 ft 1/16S, BT 4" Y.Birch squared N20E 3.2 ft.</p>
--	---	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 5-4-82
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

