

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>32</u> E. W.	<u>D9, E9, G11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-17, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D9: Found Michigan Dept. of Conservation Forestry Division Monument set by Billy D. Buckler from an original bearing tree.

Corner E9: Found Michigan, Wisconsin Power Company monument.

Corner G11: Found 1" iron pipe set by Wisconsin, Michigan Power Company.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D9: Restored at D.N.R. monument.

Corner E9: Restored at Mich. Wisconsin Power Company Monu.

Corner G11: Restored at pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D9: Michigan Dept. of Conservation Forestry Division Monument.

6" Maple N45W 17.20 ft. 1/2 S, NBT
 16" Balsam N32E 18.20 ft. 1/2 S, NBT
 7" Spruce S18E 17.70 ft. 1/2 S, NBT

Corner E9: Michigan, Wisconsin, Power Company Monu.

4" Maple N60E 8.1 ft. S21, NBT
 6" Maple S47E 17.5 ft. S28, NBT
 7" Balsam S21W 10.4 ft. S29, NBT

Corner G11: 1" iron pipe set at waters edge on Michiganme Reservoir

5" Pine S88E 166.8 ft. S34, NBT
 7" Cherry S62W 64.9 ft. S33, NBT
 Wisc. Mich. Power Co. Monu. West 10.0 ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

