

Iron Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. R. 32 E. W.	F13
2. PROPERTY CONTROLLING IN SECTION	28, T. 44 N. R. 32 E. W.	16, 15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-1, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F13: Original monument and accessories not found. Found old axel shaft driven into county road.

Corner 16: Not set on original survey nor subsequently apparently.

Corner 15: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F13: Restored at axel shaft. Unable to determine who set this axel shaft, but it fits good with other corners in area and has been used as corner for many years.

Corner 16: Established midway and on line between section corner East and 1/4 corner West.

Corner 15: Established midway and on line between section corner West and 1/4 Corner East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner F13: Old Axle shaft driven near C/L of county road.	Corner 16: Set 1" I.D. by 32" iron pipe with 4" alum. cap
12" R. Pine N18E 81.8 ft. 1/4S, NBT	7" Cherry N52W 26.6 ft. 1/16S, BT
6" R. Pine S52E 49.7 ft. 1/4S, NBT	5" Poplar S30W 24.4 ft. 1/16S, BT
7" W. Birch S50W 45.6 ft. 1/4S, NBT	5" Poplar S20E 14.8 ft. 1/16S, BT

Corner 15: Set 1" I.D. by 32" iron pipe with 4" alum. cap.

5" Sugar Plum S45W 17.1 ft. 1/16S, BT
16" Oak S45E 12.0 ft. 1/16S, BT
5" Maple N15E 21.2 ft. 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

DATE 8-17-84

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

