

Iron Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. S., R. 32 E. W.	D11
2. PROPERTY CONTROLLING IN SECTION 29	T. 44 N. S., R. 32 E. W.	3, 10
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-2, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D11: Original monument and accessories not found.

Corner 3: Not set on original survey nor subsequently apparently. Found Keweenaw Land Assc. location poster N45E 70ft.

Corner 10: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D11: Restored midway and on line between Section corners East and West.

Corner 3: Established midway and on line between Section corner North and 1/4 Corner South.

Corner 10: Established midway and on line between Section corner South and 1/4 Corner North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D11: Set 1" I.D. by 32" Iron pipe with 4" alum. cap.
18" Cedar S55W 11.7 ft. 1/4S, NBT
16" Cedar N50W 16.4 ft. 1/4S, NBT

Corner 3: Set 1" I.D. by 32" Iron pipe with 4" alum. cap.
3" W. Pine S70W 26.6 ft. 1/16S, BT
4" Maple N10E 24.7 ft. 1/16S, BT
6" Maple S54E 29.3 ft. 1/16S, BT

Corner 10: Set 1" I.D. by 60" iron pipe with 4" alum. cap.

Corner falls in open marsh beaver flooding 200ft. South of R.R. tracks. No BTs avail.
SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 8-1-84

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JULY 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET