

IRON CO

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. R. 32 E.	C10, C9
2. PROPERTY CONTROLLING IN SECTION 29	T. 44 N. R. 32 E.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-6, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner C10: Original monument and accessories not found. Found 2" I.D. by unknown length iron pipe set by unknown person.
- Corner C9: Original monument and accessories not found. Found 1" plastic pipe 49.92' North set by unknown person.
- Corner 15: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner C10: Restored at iron pipe. Pipe fits good between section corners North and South.
- Corner C9: Restored from original line tree South on top of ridge. Position checks with other corners in area.
- Corner 15: Established midway and on line between section corner West and 1/4 corner East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| Corner C10: Set 1" I.D. X 32" iron pipe with 4" alum. cap. | Corner C9: Set 1" I.D. X 32" Iron pipe with a 4" alum. cap. |
| Cedar 12 S42E 18.60ft. 1/4S, NBT                           | 16" Cedar N08W 25.6 ft. S19, NBT                            |
| Cedar 10 N08E 11.70ft. 1/4S, NBT                           | 12" Cedar S62E 26.7 ft. S29, NBT                            |
| Cedar 5 S28W 6.20ft. 1/4S, NBT                             |   |
- Corner 15: Set 1" I.D. X 32" Iron Pipe with 4" alum. cap
- |                                     |
|-------------------------------------|
| 12" Hemlock S50E 52.0 ft. 1/16S, BT |
| 6" Balsam N09W 20.8 ft. 1/16S, BT   |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 8-17-84  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

