

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Iron County

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> ^{N.} XX , R. <u>32</u> ^{E.} W.	<u>E11</u> <
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	, T. <u>44</u> ^{N.} S. , R. <u>32</u> ^{E.} W.	<u>16</u> ✓
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-3, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E11: Found two stumps that fits species, bearing and distance of original bearing trees. Stumps too rotted to distinguish scribing.

Corner 16: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E11: Restored from two stumps.

Corner 16: Established midway and on line between $\frac{1}{4}$ corner West and section corner east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E11: Set 1" I.D. by 32" iron pipe with 4" Alum. cap.
 11" Maple S20E 8.6Ft. S33, NBT
 8" Maple S20W 16.5Ft. S32, NBT
 20" W. Pine N40W 49.8Ft. S29, NBT

Corner 16: Set 1" I.D. by 32" iron pipe with 4" Alum. cap.
 8" Spruce S80E 12.0Ft. 1/16S, BT
 6" Balsam S10W 6.5Ft. 1/16S, BT
 16" W. Birch N40W 10.5Ft. 1/16S, BT
 4" Maple squared West 1.0 ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

