

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Iron County

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>32</u> E. <u>W.</u>	<u>C12</u>
2. PROPERTY CONTROLLING IN SECTION <u>31</u>	T. <u>44</u> N. <u>32</u> E. <u>W.</u>	<u>7,14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-7, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner C12: Original monument and accessories not found.
- Corner 7: Not set on original survey nor subsequently apparently.
- Corner 14: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner C12: Restored Midway and on line between section corners North and South
- Corner 7: Established Midway and on line between section corner North and $\frac{1}{4}$ corner South.
- Corner 14: Established Midway and on line between section corner South and $\frac{1}{4}$ corner North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| Corner C12: Set 1" I.D. by 32" iron pipe with 4" alum. cap.
5" Balsam N13E 11.3 Ft. $\frac{1}{4}$ S, NBT
6" Maple N54W 21.9 Ft. $\frac{1}{4}$ S, NBT
6" W. Birch S54W 24.8 Ft. $\frac{1}{4}$ S, NBT | Corner 7: Set 1" I.D. by 32" iron pipe with 4" alum. cap.
8" Sugar N57W 22.6 Ft. 1/16S, BT
12" Maple N58E 6.5 Ft. 1/16S, BT
10" Sugar S04E 10.1 Ft. 1/16S, BT
10" Y. Birch Squared S31W 2.7 Ft. |
|--|---|

- Corner 14: Set 1" I.D. by 32" iron pipe with 4" alum. cap.
 5" Hemlock S01E 6.6 Ft. 1/16S, BT
 9" Maple N66W 25.4 Ft. 1/16S, BT
 10" Maple N15E 18.7 Ft. 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

