

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 44 N. R. 32 <del>XX</del>	B1
2. PROPERTY CONTROLLING IN SECTION 6.....	T. 44 N. R. 32 <del>XX</del>	2
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19... established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19... found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner B1: Fir post (not found)  
           Fir 12 N15E 23 " "  
           Spruce 8 N34W 12 " "

No subsequent monuments found.

Corner 2: Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and or method applied in restoring or re-establishing corner:**

Corner B1: Re-established 9/16/71 proportionately on line between Sec. Cor. 39.988 ch. E and Sec. Cor. 38.598 ch. W.

Corner 2: Established 9/8/71 on line between Sec. Cor. 19.994 ch. E and 1/4 corner. 19.994 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner B1: W. Spruce 8 S63<sup>1</sup>/<sub>2</sub><sup>o</sup>E (mag.) 58.2 ft. "1/4S, NBT"  
 (Variation 1<sup>o</sup>10' East) W. Birch 4 N27<sup>o</sup>W (mag.) 12.9 ft. "1/4S, NBT"

Witnesses for Corner 2: W. Birch 16 S84<sup>o</sup>W (mag.) 14.5 ft. "1/16S, BT"  
 (Variation 0<sup>o</sup>50' East) W. Spruce 6 N86<sup>o</sup>E (mag.) 9.2 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger  
MICHIGAN REGISTERED LAND SURVEYOR

DATE January 31, 1973

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581