

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. 32 R. 32 <del>XX</del> W.	E 2
2. PROPERTY CONTROLLING IN SECTION 5	T. 44 N. 32 R. 32 <del>XX</del> W.	13 & 14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E 2:** Cedar Post (not found)  
 Sugar 8 S60W 25 " "  
 Maple 12 N55E 12 " "  
 No subsequent monuments found.

**Corners 13 & 14:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E2:** Re-established 11/4/71 proportionately on line between Sec. Cor. 39.992 ch. S and Sec. Cor. 38.473 ch. N.

**Corner 13:** Established 3/10/72 on line between 1/16 cor. 19.935 ch. W and 1/16 corner 19.935 ch. E, at calculated intersection of quarter-quarter section lines.

**Corner 14:** Established 11/4/71 on line between Sec. Cor. 19.996 ch. S and 1/4 cor. 19.996 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner E2:** Sugar Maple 7 N54°W (mag.) 5.3 ft. "1/4S, NBT"  
 Sugar Maple 7 S 8°E (mag.) 13.7 ft. "1/4S, NBT"

**Witnesses for Corner 13:** Y. Birch 9 S60°W (mag.) 15.0 ft. "1/16S, BT"  
 (Variation 0°30' East) Y. Birch 9 S82°E (mag.) 14.8 ft. "1/16S, BT"

**Witnesses for Corner 14:** Sugar Maple 7 S82°W (mag.) 24.5 ft. "1/16S, BT"  
 Basswood 14 S24°E (mag.) 31.0 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE \_\_\_\_\_ (SEAL)

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581