

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. R. 32 XX W.	B3, C2, & C3
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19__ , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19__ , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B3: Cherry post	(not found)	No subsequent monuments found
Fir 10 S20E 22	" "	
" 8 N40W 15	" "	
Corner C2: Spruce post	" "	No subsequent monuments found
Cedar 10 N55W 28	" "	
Spruce 12 S60E 23	" "	
Corner C3: Sugar post	" "	No subsequent monuments found
Fir 10 S20W 14	" "	
Hemlock 18 N30E 20	" "	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B3: Re-established 11/1/71 proportionately on line between Sec. Cor. 39.987 ch. E and Sec. Cor. 38.759 ch. W.

Corner C2: Re-established 11/4/71 proportionately on line between Sec. Cor. 40.000 ch. S and Sec. Cor. 38.490 ch. N.

Corner C3: Measurements across the north lines of Sections 5 & 6 and on the west line of Sec. 6, between original corners, indicate the true sizes of these sections as being almost exactly as reported in the original field notes. Therefore, on 9/16/71 I re-established this corner at the record distance south of an original corner 78.49 ch. N and east of one 78.77 ch. W. The position agrees with record calls to stream crossings to N, S, and E and swamp edge to N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner B3:	Red Oak 16	N20°E (mag.)	20.0 ft.	"1/4S, NBT"
	Sugar Maple 5	S31°W (mag.)	8.9 ft.	"1/4S, NBT"
Witnesses for Corner C2:	B. Spruce 6	N51°W (mag.)	18.0 ft.	"1/4S, NBT"
	B. Spruce 6	S73°E (mag.)	15.8 ft.	"1/4S, NBT"
Witnesses for Corner C3:	W. Spruce 6	N23°W (mag.)	8.4 ft.	"S6, NBT"
	Balsam 5	N29°E (mag.)	13.0 ft.	"S5, NBT"
(Variation 1°45' East)	Balsam 5	S25°E (mag.)	3.5 ft.	"S8, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY: *Arthur O. Enger* DATE: **January 31, 1973**

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**