

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. R. 32 XX W.	D3 & E3
2. PROPERTY CONTROLLING IN SECTION	T. 44 N. R. 32 XX W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D3: Ironwood post (not found) No subsequent monuments found.
 Fir 8 S20W 22 " "
 Fir 10 N30E 19 " "

Corner E3: Cedar post " " No subsequent monuments found.
 Cedar 12 S21W 24 " "
 Cedar 12 N73E 22 " "

Corner 16: Not established in original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D3: Re-established 11/4/71 on line between Sec. Corners 39.800 ch. to E and to W.
Corner E3: Measurements across the north lines of Sections 5 & 6 and on the West line of Sec. 6, between original corners, indicate the true sizes of these sections as being almost exactly as reported in the original field notes. Therefore, on 10/11/71 I re-established this corner at the record distance south of an original corner 78.48 ch. N and east of one 158.37 ch. W. The position appears consistent with stream crossings and swamp edges recorded in the original field notes. Found an old cruiser's register tree S37°E 16 lks., bearing date of 11/13/25.
Corner 16: Corner established on 11/4/71 on line between 1/4 cor. 19.900 ch. W and Sec. Cor. 19.900 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner D3: Sugar Maple 11 N53°W (mag.) 17.1 ft. "1/4S, NBT"
Sugar Maple 5 N29°E (mag.) 17.4 ft. "1/4S, NBT"
Witnesses for Corner E3: Cedar 10 S83°W (mag.) 9.2 ft. "S8, NBT"
Cedar 6 N67°E (mag.) 11.5 ft. "S4, NBT"
Cedar 8 N10°W (mag.) 7.2 ft. "S5, NBT"
Witnesses for Corner 16: Cedar 8 S34°E (mag.) 17.1 ft. "1/16S, BT"
Cedar 8 N66½°W (mag.) 37.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SEAL

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY: Arthur O. Enger DATE January 31, 1973

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581