

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. 33 R. 32 W. ^{XX}	A1 & A2
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on See Below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A1: Wood post (not found)
 Hemlock 6 N13E 33 " "
 Hemlock 6 S68W 17 " "
 Found a L.E.S. approximate corner on a squared 6" cedar N85°W 39 links.
Corner A2: Fir post (not found)
 Fir 10 S53E 16 " "
 Fir 7 N20W 12 " "
 No subsequent monuments found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A1: Re-established on 9/7/71 by double proportionate measurement between original corners 79.972 ch. W, 78.586 ch. E, 78.499 ch. S, and 39.999 ch. N. Checks with swamp edge 25 links North.
Corner A2: Re-established on 11/4/71 proportionately on line between original Sec. Cor. 40.000 ch. S and re-established township corner 38.499 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner A1: Cedar 6 S44°W (mag.) 20.4 ft. "S1, NBT"
(Variation 1°10' East) Cedar 11 S60°E (mag.) 48.1 ft. "S6, NBT"
Tamarack 6 N32°W (mag.) 24.2 ft. "S36, NBT"
Witnesses for Corner A2: W. Pine 20 N68°W (mag.) 34.3 ft. "1/4S, NBT"
W. Pine 18 S56½°W (mag.) 26.8 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 13, 1973
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581