

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. <del>XX</del> R. 32 <del>XX</del> W.	C1 & D1
2. PROPERTY CONTROLLING IN SECTION	T. 44 N. <del>XX</del> R. 32 <del>XX</del> W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER \_\_\_\_\_

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and, or subsequent restoration:**

**Corner C1:** Fir post (found)  
           Y. Birch 18 S60W 24           "  
           Cedar 18 S25E 37           "  
           Cedar 12 N28E 49 (not found)  
           B. Ash 6 N23W 4           " "

**Corner D1:** Fir post (not found) Found two later wood posts  
           Cedar 12 N45E 23 (found) in place.  
           Cedar 9 N37W 8           "

**Corner 1:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner C1:** Found point of original fir post in swamp bottom, verifying the Y. Birch BT which is still green, but has an old chopped face. Inside of tree rotted out, no marks. Also verifies Cedar 18 to SE, down, with old choppings, no marks. Corner is 40.042 ch. W of an original 1/4 corner. Set on 6/11/71.

**Corner C2:** Found plain overgrowth of upper face of BT to NW, but BT to NE is a burned stump. No marks on either. Corner is 1.00 ch. E of stream, as per original field notes, and is 40.085 ch. W of original Sec. Cor. to E and 40.042 ch. E of original Sec. Cor. to W. Set on 6/11/71.

**Corner 1:** Established 3/13/72 on line between Sec. Cor. 20.021 ch. W and 1/4 cor.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap. 20.021 ch. E

**Witnesses for Corner C1:** Cedar 11 S46°W (mag.) 30.7 ft. "S 6, NBT"  
   B. Ash 6 N43°W (mag.) 24.9 ft. "S31, NBT"  
   B. Ash 6 S39°E (mag.) 25.7 ft. "S 5, NBT"

**Witnesses for Corner D1:** Cedar 14 N49°W (mag.) 33.7 ft. "1/4S, NBT"  
   W. Birch 8 S28°W (mag.) 10.3 ft. "1/4S, NBT"

**Witnesses for Corner 1:** Sugar Maple 6 N53°E (mag.) 1.6 ft. "1/16S, BT"  
   Sugar Maple 6 S82°W (mag.) 10.1 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 13, 1973

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581