

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. R. 32 <del>XX</del> W.	A11
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 11 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Fir post	(not found)
Hemlock 14 S40W 33	" "
Sugar 8 N45E 27	" "
Spruce 12 S10E 24	" "

Found a 2" well point monumenting the corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

The well point lies on the E'ly extension of an E & W county road to the west and 4.55 ch. W'ly of the E bank of a stream. Original field notes call for a stream 4.54 ch. E to the E bank. The point has apparently been long used locally as the subject corner. Aerial photograph examination indicates this as being the likely area for the corner, also. Therefore, I accepted monument as the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Replaced the well point with a 1" I.D. x 36" iron pipe with 4" aluminum cap.

Sugar Maple	S83°E (mag.)	10.5 ft.	"S31, NBT"
Red Maple	N15°W (mag.)	17.4 ft.	"S25, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 13, 1973

*Arthur O. Enger*  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581