

**SURVEY &
REMONUMENTATION**

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:26

L.C. Records 6.7 P.119

Gilbert J. Pisoni
REGISTERED DEEDS

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>A-3</u> ✓
	T <u>44N</u> R <u>33W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sec. 6 and 7, T44N, R32W
Section Corner Sec. 1 and 12, T44N, R33W

I, Gary L. Pisoni, in a field survey on November 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, in August of 1846.
Original Corner: Sugar Post
Original Bearing Trees:

W. Pine	34"	S70°E	13 links(8.58 feet)
Sugar	8"	N271/2°W	27 links(17.82 feet)

In 1849, Zelotes B. Searls, U.S. Deputy Surveyor, made a new bearing tree:

W. Pine	40"	N12°E	30 links(19.80 feet)
---------	-----	-------	----------------------

On 6-6-57, Billy D. Buckler, RLS with the Michigan Dept. Of Natural Resources, restored the corner position using bearing and distance from recovered White Pine bearing trees. Set a 4 inch diameter brass capped pipe monument, 12 inches above the ground. Recorded in Land Corner Certificate L. 2, Page 183, on December 10th, 1976.

1957 Bearing Trees:

White Pine(stump)	24"	S22°W	50.49 feet
White Spruce	8"	S30°E	48.51 feet
Aspen	5"	N20°E	33.00 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Decayed remains of original white pine B.T.s are still evident.

On 11-3-97, found monument as set by Billy D. Buckler in 1957, and the following bearing trees;

White Pine(stump)	24"	S25°W	51.8 feet
White Spruce	10"	S28°E	48.79 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Spruce	6"	N54°E	25.10 feet
Aspen	7"	S16°W	39.57 feet
W. Spruce	16"	N76°W	25.08 feet
Steel Sign Post		S80°E	0.75 feet



IRON COUNTY APPROVED
Gary L. Pisoni 11-11-97
IRON COUNTY REPRESENTATIVE

97-14
Signed by *Gary L. Pisoni* Date November 7, 1997
Surveyor's Michigan License No. 27457