

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

97 DEC 23 PM 1:26

L.C. Records L.7 P.120

Gilbert J. Pisoni
 REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>B-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner Sec. 6 and 7, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3		●											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in July of 1849 by Zelotes B. Searls, US Deputy Surveyor.
 Original Corner: Cherry Post
 Original Bearing Trees;

Fir	10"	S20° E	22 links(14.52 feet)
Fir	8"	N40° W	15 links(9.90 feet)

On 11-1-71, Arthur O. Enger, RLS with the Michigan Dept. Of Natural Resources, restored the corner position proportionately and on line between the Section Corner 39.987 chains to the East and the Section Corner 38.759 chains to the West. Set a 4 inch diameter aluminum capped pipe monument, 3 feet long, 12 inches above ground. Recorded in Land Corner Certificate L. 1, Pages 191-192, on June 27th, 1973.
 1971 Bearing Trees;

Red Oak	16"	N20° E	20.0 feet
Sugar Maple	5"	S31° W	8.9 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.
 On 11-3-97 found the monument as set by Arthur O. Enger, and the following bearing trees;

Red Oak	18"	N23° E	20.31 feet
Sugar Maple(DBL)	8"	S32° W	9.00 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	8"	S86° E	41.90 feet
Sugar Maple	16"	N40° W	28.98 feet
Steel Sign Post		N87° W	0.75 feet

PEER GROUP APPROVED

Gary L. Pisoni 11-11-97
 IRON COUNTY REGISTERED LAND SURVEYOR

97-15
 Signed by Gary L. Pisoni

Date November 7, 1997

Surveyor's Michigan License No. 27457