

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

97 DEC 23 PM 1:26

L.C. Records L.7 P.126

Gilbert Stebbins
 REGISTER OF DEEDS

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>B-7</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner Section 18 and 19, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.
 Original Corner; Maple Post
 Original Bearing Trees;

Hemlock	24"	South	8 links (5.28 feet)
Maple	6"	N56° W	26 links (17.16 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T. found.

On 11-5-97, found 2 old squared cedar posts marking corner position. One being 3" in diameter and the other is 4" in diameter. Also found a new squared pickett, painted blue, from which a location tag bears N20 E, 10.2 feet. I accept the old wood post as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 3/4" outside diameter aluminum rod monument, 3 feet long, 2 inches above the ground, with an aluminum cap stamped as follows; Iron County Remonumentation, T44N, R32W, 1/4, S18, S19, 1997, RLS 27457. Blazed and scribed the following new bearing trees; (All measurements taken to a nail in side of tree)

Red Maple	8"	N61° E	44.00 feet
Red Maple	8"	S68° E	42.62 feet
Sugar Maple	7"	S02° E	5.02 feet
Sugar Maple	7"	N60° W	3.56 feet
Steel Sign Post		S75° E	1.02 feet

PEER GROUP APPROVED

Gary L. Pisoni 11-11-97
 IRON COUNTY REGISTERED LAND SURVEYOR

97-21
 Signed by *Gary L. Pisoni*
 Surveyor's Michigan License No. 27457

Date November 7, 1997

