

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:27

L.C. Records L. 9 P. 129

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Gary L. Pisoni
REGISTER OF DEEDS

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>R32W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sec. 19 and 30, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.
Original Corner; Cedar Post
Original Bearing Trees;

Spruce	18"	S40°W	11 links (7.26 feet)
Cedar	20"	N50°E	18 links (11.88 feet)

On 8-17-84, Keith L. Sackett, RLS with the Michigan Dept. Of Natural Resources found a 1" Iron Rod set by unknown person. Restored corner position as it fits well with other corners in the area. Recorded in Land Corner Certificate L.5, Page 80, on September 14, 1984.
1984 Bearing Trees;

Balsam	7"	N44°W	24.8 feet
W. Pine	22"	N26°E	27.3 feet
Maple	5"	S12°E	13.7 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.
On 11-5-97, found iron rod as described above and a 3" squared post marking the corner position.
Found the following bearing trees;

Balsam	8"	N39°W	25.01 feet
W. Pine	23"	N29°E	27.70 feet
Maple	8"	S15°E	13.98 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron bar with a 3/4" outside diameter aluminum rod monument, 4 feet long, 2 inches above the ground, with a 3" aluminum cap stamped as follows; Iron County Remonumentation; T44N, R32W, 1/4, S19, S30, 1997, RLS 27457. Blazed and scribed the following new bearing trees; (All measurements taken to a nail in side of tree)

Red Maple	11"	S68°W	44.15 feet
Steel Sign Post		N75°E	0.85 feet

PEER GROUP APPROVED
Gary L. Pisoni 11-11-97
IRON COUNTY REGISTERED SURVEYOR

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

97-24
Signed by *Gary L. Pisoni* Date November 7, 1997
Surveyor's Michigan License No. 27457

