

**SURVEY & REMONUMENTATION**

**JAN 13 1998**

**SECTION**

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

97 DEC 23 PM 1:29  
*L.C. Records L.P. 149*

*Gilbert Stiles*  
REGISTERED DEEDS

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Sections 7, 8, 17, 18, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.

Original Corner; Cedar Post  
Original Bearing Trees;

Sugar	10"	S25° W
Sugar	18"	N55° E

PEER GROUP APPROVED

*Gary L. Pisoni 12-1-97*  
IRON COUNTY REPRESENTATIVE

37 lks.(24.42 feet)  
25 lks.(16.50 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence was recovered.

I restored the corner position by double proportionate methods between the East quarter Corner of Section 7 and the Southeast Corner of Section 18 and between the Southwest Corner of Section 7 and the Southeast Corner of Section 9.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 3/4 inch outside diameter aluminum rod monument, 3 feet long, 3 inches above the ground surface, with a 3 inch diameter aluminum cap stamped as follows; Iron County Remonumentation, T44N, R32W, S7, S8, S17, S18, 1997, RLS 27457. Blazed and scribed the following new bearing trees; (Measurements are taken to a nail in side of tree)

White Spruce	14"	N60° E	23.05 feet
Red Maple	8"	S08° E	38.13 feet
Red Maple	9"	S46° W	28.45 feet
Sugar Maple	8"	S84° W	25.65 feet
Steel Sign Post		S80° E	0.60 feet

97-44  
Signed by Gary L. Pisoni  
Surveyor's Michigan License No. 27457

Date November 29, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971

